Name:Jaira Biane Maculada	Date Performed:11/30/23
Course/Section:CPE232/CPE31S6	Date Submitted:11/30/23
Instructor: Dr. Jonathan V. Taylar	Semester and SY: 1st Sem(2023-2024)
Activity 14: OpenStack Installation (Keystone, Glance, Nova)	

1. Objectives

Create a workflow to install OpenStack using Ansible as your Infrastructure as Code (laC).

2. Intended Learning Outcomes

- 1. Analyze the advantages and disadvantages of cloud services
- 2. Evaluate different Cloud deployment and service models
- 3. Create a workflow to install and configure OpenStack base services using Ansible as documentation and execution.

3. Resources

Oracle VirtualBox (Hypervisor)

1x Ubuntu VM or Centos VM


4. Tasks

- 1. Create a new repository for this activity.
- 2. Create a playbook that converts the steps in the following items in https://docs.openstack.org/install-guide/
 - a. Keystone (Identity Service)
 - b. Glance (Imaging Service)
 - c. Nova (Compute Service)
 - d. Create different plays in installing per server type (controller, compute etc.) and identify it as a group in the Inventory file.
 - e. Add, commit and push it to your GitHub repo.

5. Output (screenshots and explanations)

Task 1: Create a File

1. Create a new repository for this Hands-On Activity.



2. Create the ansible.cfg and inventory file (*must include one Ubuntu*)

```
jai@workstation: ~/CPE232_HOA14.1

File Edit View Search Terminal Help

GNU nano 2.9.3 ansible.cfg

[defaults]
inventory = inventory
host_key_checking = False

deprecation_warnings = False

remote_user = jai
private_key_file = ~/.ssh/
```

```
jai@workstation: ~/CPE232_HOA14.1

GNU nano 2.9.3 inventory

[Keystone]
192.168.56.102

[Glance]
192.168.56.102

[Nova]
192.168.56.102
```

Task 2: Create Playbook for Installing OpenStack

1. Create a playbook and name it install_openstack.yml.

jai@workstation: ~/CPE232_HOA14.1 File Edit View Search Terminal Help install_openstack.yml GNU nano 2.9.3 hosts: all become: true pre_tasks: - name: Install updates (Ubuntu) apt: upgrade: dist update_cache: yes changed_when: false hosts: Keystone become: true roles: - role: Keystone hosts: Glance become: true roles: - role: Glance hosts: Nova become: true roles: - role: Nova

Code explanation:

It instructs Ansible to run tasks on all hosts, become a privileged user, and execute a pre-task. The pre-task installs updates on Ubuntu using the 'apt' module, specifying a distribution upgrade while suppressing changes indication for brevity.

```
GNU nano 2.9.3 install_openstack.yml

---
- hosts: all
become: true
pre_tasks:
- name: Install updates (Ubuntu)
apt:
    upgrade: dist
    update_cache: yes
    changed_when: false
```

2. Save the file and exit.

Task 3: Create Roles

1. Create a new directory and name it "roles". Enter the roles directory and create new directories: Keystone, Nova, and Glance. For each directory, create a directory and name it tasks.

For Keystone

```
jai@workstation:~/CPE232_HOA14.1/roles$ mkdir Keystone
jai@workstation:~/CPE232_HOA14.1/roles$ cd Keystone
jai@workstation:~/CPE232_HOA14.1/roles/Keystone$ mkdir tasks
jai@workstation:~/CPE232_HOA14.1/roles/Keystone$ cd tasks
jai@workstation:~/CPE232_HOA14.1/roles/Keystone/tasks$
```

For Nova

```
jai@workstation:~/CPE232_HOA14.1/roles$ mkdir Nova
jai@workstation:~/CPE232_HOA14.1/roles$ cd Nova
jai@workstation:~/CPE232_HOA14.1/roles/Nova$ mkdir tasks
jai@workstation:~/CPE232_HOA14.1/roles/Nova$ cd tasks
jai@workstation:~/CPE232_HOA14.1/roles/Nova/tasks$
```

For Glance

```
jai@workstation:~/CPE232_HOA14.1/roles$ mkdir Glance
jai@workstation:~/CPE232_HOA14.1/roles$ cd Glance
jai@workstation:~/CPE232_HOA14.1/roles/Glance$ mkdir tasks
jai@workstation:~/CPE232_HOA14.1/roles/Glance$ cd tasks
jai@workstation:~/CPE232_HOA14.1/roles/Glance/tasks$
```

Tree for roles

```
jai@workstation:~/CPE232_H0A14.1/roles$ tree

Glance
tasks
Keystone
tasks
Nova
tasks
```

2. In each of the tasks for the three directory (*Keystone, Nova, Glance*), create another file and name it main.yml

For Keystone

```
jai@workstation:~/CPE232_HOA14.1/roles$ cd Keystone/tasks
jai@workstation:~/CPE232_HOA14.1/roles/Keystone/tasks$ sudo nano main.yml
jai@workstation:~/CPE232_HOA14.1/roles/Keystone/tasks$
```

For Nova


```
jai@workstation:~/CPE232_HOA14.1/roles$ cd Nova/tasks
jai@workstation:~/CPE232_HOA14.1/roles/Nova/tasks$ sudo nano main.yml
```

For Glance jai@workstation:~/CPE232_H0A14.1/roles\$ cd Glance/tasks jai@workstation:~/CPE232_H0A14.1/roles/Glance/tasks\$ sudo nano main.yml Tree for roles jai@workstation:~/CPE232_H0A14.1/roles\$ tree Glance tasks main.yml Keystone tasks main.yml Nova main.yml

3. Copy the code to the main.yml of the each subdirectory.

6 directories, 3 files

For Keystone



```
Blame 92 lines (75 loc) - 3.21 KB
ode
                                                                                                Raw C
                  recurr [mema]
       - name: Create a seperate apache config to serve our python script over HTTP
           dest: /etc/apache2/conf-available/wsgi.conf
              WSGIScriptAlias /test_wsgi /var/www/html/test_script.py
       #- name: restart apache server
       - name: install the keystone package
           name: keystone
         when: ansible_distribution == "Ubuntu"
       #editing the [database] /etc/keystone/keystone.conf
       #LINK: docs.openstack.org/keystone/yoga/install/keystone-install-ubuntu.html
       # shell: su -s /bin/sh -c "keystone-manage db_sync" keystone
       - name: initializing the fernet repositories (1)
         shell: keystone-manage fernet_setup --keystone-user keystone --keystone-group keystone
         when: ansible_distribution == "Ubuntu"
- name: initializing the fernet repositories (2)
 shell: keystone-manage credential_setup --keystone-user keystone --keystone-group keystone
# shell: keystone-manage bootstrap --bootstrap-password 1234 --bootstrap-admin-url http://controller:5000/v3/
- name: configure apache http server
   dest: /etc/apache2/apache2.conf
    ServerName controller
 when: ansible_distribution == "Ubuntu"
 name: configuring administrative account by setting the proper environmental variables (1)
 shell: export OS_USERNAME=admin

    name: configuring administrative account by setting the proper environmental variables (2)

 shell: export OS_PASSWORD=1234
 name: configuring administrative account by setting the proper environmental variables (3)
 shell: export OS_PROJECT_NAME=admin
 name: configuring administrative account by setting the proper environmental variables(4)
 shell: OS_USER_DOMAIN_NAME=Default
```

```
- name: configuring administrative account by setting the proper environmental variables(5)
    shell: OS_PROJECT_DOMAIN_NAME=Default
- name: configuring administrative account by setting the proper environmental variables(6)
    shell: OS_AUTH_URL=http://controller:5000/v3
- name: configuring administrative account by setting the proper environmental variables (7)
    shell: OS_IDENTITY_API_VERSION=3
- block:
    - name: Verifying if already active and running the keystone.
    shell: keystone-manage --help
    register: keystone_service
- debug:
    msg="{{ keystone_service }}"
```

For Nova

```
Blame
- name: install the packages
    name: nova-compute
  when: ansible_distribution == "Ubuntu"
- name: configuring RabbitMQ message queue access
    dest: /etc/nova/nova.conf
      [DEFAULT]
      tranport_url = rabbit://openstack:1234@controller
      my_ip = 192.168.56.103
- name: configuring identity service access (1)
  copy:
    dest: /etc/nova/nova.conf
      [api]
      auth_strategy = keystone
 - name: configuring identity service access (2)
    dest: /etc/nova/nova.conf
```

```
[keystone_authtoken]
     www_authenticate_uri = http://controller:5000/
     auth_url = http://controller:5000/
     memcached_servers = controller:11211
     auth_type = password
     project_domain_name: Default
     user_domain_name = Default
     project_name = service
     username = nova
     password = 1234
- name: enable and configure remote console access
   dest: /etc/nova/nova.conf
     enabled = true
     server_listen = 0.0.0.0
     server_proxyclient_address = $my_ip
     novncproxy_base_url = http://controller:6080/vnc_auto.html
- name: configure the location of the image service API
    [glance]
```

```
- name: configure the lock path
   dest: /etc/nova/nova.conf
     [solo_currency]
     lock_path = /var/lib/nova/tmp
- name: configure the placement API
   dest: /etc/nova/nova.conf
     [placement]
     region_name = RegionOne
     project_domain_name = Default
     project_name = service
     auth_type = password
     user_domain_name = Default
     auth_url = http://controller:5000/v3
     username = placement
     password = 1234
- name: configuring to make the computer node to support hardware acceleration
   dest: /etc/nova/nova-compute.conf
   - name: restarting the computer service
     shell: service nova-compute restart
   - block:
     - name: Verifying if already running and active the nova-compute.
       shell: systemctl status nova-compute
       register: novacompute_service
     - debug:
        msg="{{ novacompute_service }}"
```

For Glance

```
- name: install and configure components of glance
    name: glance
  when: ansible_distribution == "Ubuntu"
 #editing the [database] /etc/glance/glance-api.conf
 - name: configuring database access
    dest: /etc/glance/glance-api.conf
      [database]
      connection = mysql+pymysql://glance:1234@controller/glance
       [keystone_authtoken]
       www_authenicate_uri = http://controller:5000
       auth_url = http://controller:5000
       memcached_servers = controller:11211
       auth_type = password
      project_domain_name = Default
       user_domain_name = Default
       project_name = service
      username = glance
     [paste_deploy]
- name: configuring the local file system store and location of image files
   dest: /etc/glance/glance-api.conf
```

```
[paste_deploy]
    flavor = keystone

- name: configuring the local file system store and location of image files
copy:
    dest: /etc/glance/glance-api.conf
    content: |
        [glance_store]
        stores = file, http
        default_store = file
        filesystem_store_datadir = /var/lib/glance/images/

- name: configuring the access to keystone
copy:
    dest: /etc/glance/glance-api.conf
    content: |
        [oslo_limit]
        auth_url = http://controller:5000
        auth_type = password
        user_domain_id = default
        username = MY_SERVICE
        system_scope = all
        password = 1234
        endpoint_id = ENDPOINT_ID
        region_name = RegionOne
```

```
- name: enable per-tenant quotas
       dest: /etc/glance/glance-api.conf
mbox content: |
         [DEFAULT]
          use_keystone_quotas = True
    #- name: MY_SERVICE read access to systemscope resources
      when: ansible_distribution == "Ubuntu"
    - name: restart the image services
      shell: service glance-api restart
      when: ansible_distribution == "Ubuntu"
      - name: Verifying if already installed Glance.
       shell: glance --version
       register: glance_version
      - debug:
      - debug:
          msg="{{ glance_version }}"
      - name: Verifying if already active and running the Glance.
       shell: systemctl status glance-api
        register: glance_service
      - debug:
          msg="{{ glance_service }}"
```

Task 4: Run and Verify

1. Run the command ansible-playbook - - ask-become-pass install_openstack.yml to completely install the OpenStack.

jai@workstation: ~/CPE232_HOA14.1/roles/Nova/tasks jal@workstation:~/CPE232_HOA14.1/roles/Keystone/tasks\$ cd ../../.. jai@workstation:~/CPE232_HOA14.1\$ ansible-playbook --ask-become-pass install_openstack.yml BECOME password: ok: [192.168.56.102] TASK [Keystone : Install the prerequisites for mod_wsgi] *********************** changed: [192.168.56.102] TASK [Keystone : Create a seperate apache config to serve our python script over HTTP] *** changed: [192.168.56.102] TASTerminatone : initializing the fernet repositories (1)] ********************* changed: [192.168.56.102] TASK [Keystone : initializing the fernet repositories (2)] ********************* changed: [192.168.56.102]

```
jai@workstation: ~/CPE232_HOA14.1/roles/Nova/tasks
changed: [192.168.56.102]
TASK [Keystone : configuring administrative account by setting the proper environmental variables (1)
TASK [Keystone : configuring administrative account by setting the proper environmental variables (2)
hanged: [192.168.56.102]
TASK [Keystone : configuring administrative account by setting the proper environmental variables (3)
hanged: [192.168.56.102]
TASK [Keystone : configuring administrative account by setting the proper environmental variables(4)]
changed: [192.168.56.102]
TASK [Keystone : configuring administrative account by setting the proper environmental variables(5)]
changed: [192.168.56.102]
TASK [Keystone : configuring administrative account by setting the proper environmental variables(6)]
changed: [192.168.56.102]
TASK [Keystone : configuring administrative account by setting the proper environmental variables (7)
changed: [192.168.56.102]
TASK [Keystone : Verifying if already active and running the keystone.] *******
```

jai@workstation: ~/CPE232_HOA14.1/roles/Nova/tasks

```
changed: [192.168.56.102]
changed: [192.168.56.102]
TASK [Glance : configuring the local file system store and location of image files] ***
changed: [192.168.56.102]
changed: [192.168.56.102]
changed: [192.168.56.102]
changed: [192.168.56.102]
changed: [192.168.56.102]
ok: [192.168.56.102] => {
   "changed": true,
  "cmd": "glance --version", "delta": "0:00:00.256231",
Show Applications 11-30 18:12:40.131418",
```

```
jai@workstation: ~/CPE232_HOA14.1/roles/Nova/tasks
         "cmd": "glance --version", "delta": "0:00:00.256231",
         "start": "2023-11-30 18:12:39.875187",
"stderr": "2.9.1",
TASK [Glance : Verifying if already active and running the Glance.] **********
changed: [192.168.56.102]
Help
          changed": true,
         "cmd": "systemctl status glance-api",
"delta": "0:00:00.054612",
"end": "2023-11-30 18:12:40.414857",
         "failed": false,
"msg": "",
"rc": 0,
         "start": "2023-11-30 18:12:40.360245",
"stderr": "",
```

jai@workstation: ~/CPE232_HOA14.1/roles/Nova/tasks

```
changed: [192.168.56.102]
anged: [192.168.56.102]
Terminal
TASK [Nova : configuring to make the computer node to support hardware acceleration] ***
changed: [192.168.56.102]
changed: [192.168.56.102]
```

```
TASK [Nova : Verifying if already running and active the nova-compute.] *********

changed: [192.168.56.102]

TASK [Nova : debug] ************

ok: [192.168.56.102] => {
    "msg": {
        "changed": true,
        "md": "systemctl status nova-compute",
        "delta": "0e0:00e.054407",
        "end": "2023-11-30 18:13:45.985907",
        "falled": false,
        "msg": "",
        "rc": 0,
        "statrt": "2023-11-30 18:13:45.931500",
        "statrt": "2023-11-30 18:13:45.931500",
        "stderr": "",
        "stdour": "@nova-compute.service - OpenStack Compute\n Loaded: loaded (/lib/systemd/system/nova-compute.service; enabled; vendor preset: enabled)\n Active: active (running) since Thu 2023-11-30 18:13:45 PST; 251ms ago\n Main PID: 24896 (nova-compute)\n Tasks: 1 (limit: 4656)\n Group: /system.slice/nova-compute.service\n L-24896 /usr/bin/python2 /usr/bin/nova-compute --config-file=/etc/nova/nova-compute.service; enabled; vendor preset: enabl
```

2. Show the screenshot of the Keystone, Nova, and Glance that are working.

Keystone


```
WARNING: apt does not have a stable CLI interface. Use with caution in scripts.
keystone/bionic-updates,bionic-updates,bionic-security,bionic-security,now 2:13
.0.4-Oubuntu1 all [installed]
python-keystone/bionic-updates,bionic-updates,bionic-security,bionic-security,now 2:13.0.4-Oubuntu1 all [installed,automatic]
python-keystoneauth1/bionic,bionic,now 3.4.0-Oubuntu1 all [installed,automatic]
python-keystoneclient/bionic,bionic,now 1:3.15.0-Oubuntu1 all [installed,automatic]
python-keystonemiddleware/bionic,bionic,now 4.21.0-Oubuntu1 all [installed,automatic]
```

Glance

```
Thu 18:20
ies 🔚 Terminal 🔻
                                    jai@server1: ~
 File Edit View Search Terminal Help
jai@server1:~$ sudo systemctl status glance-api
🔵 glance-api.service - OpenStack Image Service API
   Loaded: loaded (/lib/systemd/system/glance-api.service; enabled; vendor pres
   Active: active (running) since Thu 2023-11-30 18:12:39 PST; 7min ago
 Main PID: 14471 (glance-api)
    Tasks: 3 (limit: 4656)
   CGroup: /system.slice/glance-api.service
—14471 /usr/bin/python2 /usr/bin/glance-api --config-file=/etc/glan
            -14516 /usr/bin/python2 /usr/bin/glance-api --config-file=/etc/glan
            __14517 /usr/bin/python2 /usr/bin/glance-api --config-file=/etc/glan
Nov 30 18:12:39 server1 glance-api[14471]: /usr/lib/python2.7/dist-packages/pas
Nov 30 18:12:39 server1 glance-api[14471]:
                                               return pkg_resources.EntryPoint.pa
Nov 30 18:12:39 server1 glance-api[14471]: /usr/lib/python2.7/dist-packages/pas
Nov 30 18:12:39 server1 glance-api[14471]:
                                              return pkg_resources.EntryPoint.pa
Nov 30 18:12:40 server1 glance-api[14471]: /usr/lib/python2.7/dist-packages/pas
Nov 30 18:12:40 server1 glance-api[14471]:
                                              return pkg_resources.EntryPoint.pa
Nov 30 18:12:40 server1 glance-api[14471]: /usr/lib/python2.7/dist-packages/pas
Nov 30 18:12:40 server1 glance-api[14471]: return pkg_resources.EntryPoint.pa
Nov 30 18:12:40 server1 glance-api[14471]: /usr/lib/python2.7/dist-packages/pas
Nov 30 18:12:40 server1 glance-api[14471]:
                                             val = callable(*args, **kw)
lines 1-20/20 (END)
```

3. Upload it in the github.

```
jai@workstation:~/CPE232_HOA14.1$ git add *
jai@workstation:~/CPE232_HOA14.1$ git commit -m "OpenStack Installation"
[main da2bc94] OpenStack Installation
 6 files changed, 344 insertions(+)
 create mode 100644 ansible.cfg
 create mode 100644 install_openstack.yml
 create mode 100644 inventory
 create mode 100644 roles/Glance/tasks/main.yml
 create mode 100644 roles/Keystone/tasks/main.yml
 create mode 100644 roles/Nova/tasks/main.yml
jai@workstation:~/CPE232_HOA14.1$ git push origin
Counting objects: 15, done.
Delta compression using up to 2 threads.
Compressing objects: 100% (9/9), done.
Writing objects: 100% (15/15), 3.90 KiB | 3.90 MiB/s, done.
Total 15 (delta 0), reused 0 (delta 0)
To github.com:jaebieeee/CPE232_HOA14.1.git
  Show Applications 94 main -> main
 al@workstation:~/CPE232 HOA14.1$
```



GITHUB LINK: https://github.com/jaebieeee/CPE232 HOA14.1.git

Reflections:

Answer the following:

1. Describe Keystone, Glance and Nova services.

In OpenStack, Keystone is the identity service, managing user authentication. Glance is the image service, handling virtual machine images. Nova is the compute service, orchestrating the creation and management of virtual machines. Together, they form the backbone of OpenStack, ensuring secure access, efficient image storage, and seamless virtual machine operation for cloud computing.

Conclusion:

In this activity, I was able to encounter the Keystone, Nova, and Glance. Compared to the last activity, which also focuses on OpenStack, it is more complicated to understand the entire concept of the three. In the journey of exploring cloud services, we've unveiled a realm of possibilities and challenges. Embracing the advantages of flexibility and scalability, we also faced the intricacies of security concerns and potential downtime. By delving into diverse cloud deployment and service models, we gained a nuanced understanding of tailoring solutions to specific needs. Notably, orchestrating an OpenStack installation through Ansible illuminated the power of automation and meticulous documentation. The lesson echoes: the cloud's potential is boundless, but success lies in navigating its terrain wisely. It's not just about technology; it's about a mindful fusion of innovation, adaptability, and strategic decision-making.